



Case Study

BlazeMaster® Fire Sprinkler System retrofit readies residence halls for back to school.

Type of Construction:
Dormitory

Installation Type:
Retrofit

Location:
Winston-Salem,
North Carolina

Scope of Project:
Heads: 1,600
Sq. Feet: 232,000
Stories: 3 to 4

Fire Sprinkler Contractor:
Worsham Sprinkler



When five students died tragically in a fire at the University of North Carolina, Wake Forest University, Winston-Salem, N.C., embarked on an ambitious program to retrofit all campus housing with fire sprinkler systems.

The university was limited to work on the project when the number of students requiring campus housing was greatly reduced, from mid-May to mid-August. During the first summer, two buildings were completed, then four in the summer of 1998, and six in 1999.

The first residence hall at Wake Forest was retrofitted with a steel fire sprinkler system, which proved to be time and labor intensive. The design of the steel fire sprinkler system required extensive field survey, which could not be performed until students vacated the residence halls for summer recess. And, design and fabrication pushed the installation period perilously close to the date students returned from summer vacation.

Other challenges with retrofitting older residence halls include installation tight against exposed ceilings, installation in small spaces above existing dropped ceilings, and field revisions due to unforeseen obstructions.

Soffiting, painting and alarm work had to be added to the already tight construction schedule. As a result, Wake Forest University officials were forced to consider limiting the size and scope of the work scheduled for each summer to ensure completion before the fall semester.

Contractor Recommends BlazeMaster® CPVC Fire Sprinkler Systems

When Worsham Sprinkler, Charlotte, N.C., won the contract for the Wake Forest Student Apartments project in 1997, they recommended an alternative to steel fire sprinkler pipe to alleviate some of the challenges faced in the first installation. Worsham had used BlazeMaster® CPVC pipe in similar jobs, and they knew it led to faster, easier installations.

“We advised Wake Forest to use a BlazeMaster® CPVC System to ensure that the installation could be done on time and without the problems associated with the design and fabrication of steel pipe. We also wanted to demonstrate to Wake Forest the features and benefits of a BlazeMaster® Fire Sprinkler System,” said Carl Jackson, Vice President for the Charlotte office of Worsham.

Following the Student Apartments installation, Wake Forest sent some of its staff to visit a nearby university, where BlazeMaster® Fire Sprinkler Systems were being used for a dormitory retrofit. Recognizing that the retrofit proved successful even in large, older buildings, the Wake Forest staff approved BlazeMaster® Fire Sprinkler Systems for all campus housing.



BlazeMaster® CPVC Pipe Enters Residence Halls

In 1998, Worsham retrofitted two residence halls, totaling 100,000 sq. ft., with BlazeMaster® CVPC pipe and fittings. During the summer of 1999, they completed three more residence halls retrofits; Kitchin, Poteat and Huffman, a total of 132,000 sq. ft.



Because CPVC pipe does not require pre-fabrication, the design time was reduced and field installation began immediately after the students vacated the residence halls. With CPVC pipe, field changes were made quickly and easily. BlazeMaster® pipe was installed in many spaces where rigid, threaded steel pipe would have required difficult, costly cutting and re-threading.

Other advantages of BlazeMaster® CPVC pipe are long-term reliability due to its corrosion resistance, low flame spread, low smoke emission levels and a 50-year life expectancy based upon a safety factor of 2. CPVC piping lasts much longer and requires less maintenance compared to metallic piping systems.



In one summer, Worsham installed approximately 1,600 sprinkler heads, consisting of 800 heads to NFPA 13 standards in Kitchin and 800 heads to NFPA 13R standards in Poteat and Huffman. The entire fire protection retrofit, including sprinklers, smoke detection, painting and clean up, took just eight weeks during summer recess.

According to Chris Lyons, job foreman, "No way could we have met this schedule without the CPVC Piping System."



Fire Sprinklers Put To The Test

In March 1999, at 8:30 p.m., a smoke detector tripped the fire alarm in one of the Wake Forest student residences. When the fire department arrived at the scene, they found one sprinkler head had operated and extinguished the fire. No one was injured. Total damage was under \$10,000.

According to David Brown, the manager of Safety and Environmental Affairs at Wake Forest University, "We realized just how dangerously close we came to a tragedy that night. We believe the safety of our students comes before any price and the fire sprinkler retrofits were a small cost compared to the peace of mind of the parents of our students and our school administrators."

Another Summer Retrofit

In the summer of 2000, Wake Forest completed the final four campus housing retrofits. The ambitious program started in 1997 has been an unqualified success. The total cost of the fire protection program was minimal compared to the cost of losing students and damaging buildings as a result of fire.

The information contained herein is believed to be reliable, but no representations, guarantees or warranties of any kind are made as to its accuracy, suitability for particular applications or the results to be obtained therefrom. The information is based on laboratory work with small-scale equipment and does not necessarily indicate end product performance. Because of the variations in methods, conditions and equipment used commercially in processing these materials, no warranties or guarantees are made as to the suitability of the products for the applications disclosed. Full-scale testing and end product

performance are the responsibility of the user. Noveon shall not be liable for and the customer assumes all risk and liability of any use or handling of any material beyond Noveon's direct control. THE SELLER MAKES NO WARRANTIES, EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Nothing contained herein is to be considered as permission, recommendation, nor as an inducement to practice any patented invention without permission of the patent owner.

For more information, call 888-234-2436, e-mail blazemaster@blazemaster.com or visit www.blazemaster.com

**Now listed
for more types
of applications
than any other
non-metallic
system.**